


ALBA SYNCHROTRON LIGHT SOURCE, Barcelona Spain, 27 September 2023

ESRF-EBS Implementation, Commissioning and Restart of user operation

Jean-Luc Revol

On behalf of the EBS Accelerator Project Team



The European Synchrotron



My position at ESRF:

- Operation Manager *(From January 2002)*
- Engineer in the Radio-Frequency Group *(October 1989 to January 2002)*

My involvement in EBS:

- ✓ Coordinator of the accelerator parts of the Purple Book (Phase 1), White Paper and Orange Book (Phase2)

- ✓ Coordinator of the TDS phase, including budget and planning

- ✓ Coordinator in the Accelerator Project Office during implementation

- ✓ EBS procurement coordinator

Preparation and follow-up of the budget

Follow-up of the contracts execution and deliveries

- ✓ Coordination of Equipment set-up and commissioning


- ✓ Coordination of the return to operation







- **ESRF-EBS Project overview [20 mn]**
 - Objectives (Lattice, technical constraints,..)
 - EBS time line
 - Accelerator main components
 - Design & procurement
 - Assembly Phase & Mockup Cell
 - Upgrades and preparatory work prior shutdown
 - Logistics
- **Shutdown activities [PPT Film 5 mn]**
 - Dismantling
 - Installation in the tunnel
 - Installation in the technical zones
- **Restart [20 mn]**
 - Beam commissioning
 - Performance
 - User operation
- **Lessons learned [10 mn]**
- **Conclusion**

Legal status: Private civil company subject to French law



- Decrease the horizontal emittance
- Increase the source brilliance
- Increase the source coherence






ESRF-EBS
Extremely Brilliant Source

ESRF Extremely Brilliant Source ESRF-EBS – 150 M€ (2015-2022)




- ~100 times more brilliant and coherent X-rays
- Programme to exploit the qualities of this new and unique extremely brilliant X-ray source:
 - Creation of new beamlines
 - Innovative detector programme
 - « Data as a Service » strategy

Budget for the source only: 104 M€





ESRF-EBS: BRILLIANCE AND COHERENCE INCREASE




Hor. Emittance [nm]	4	0.135
Vert. Emittance [pm]	4	5
Energy spread [%]	0.1	0.09
$\beta_x[m]/\beta_z[m]$	37/3	6.9/2.6

Source performances
improved by a factor 50 to 100




THE ESRF-EBS UPGRADE OBJECTIVES AND CONSTRAINTS



Main design constraints were:

- Horizontal equilibrium emittance < 150 pm.rad
- Keep the electron energy (6 GeV)
- Fit existing tunnel and infrastructure
- Maintain IDs and bending magnets beamlines
- Use existing injector chain
- Preserve the time structure operation and a multibunch current of 200 mA
- Minimize power consumption
- Maintain standard User-Mode Operations until the day of shut-down for installation
- Limit the downtime for installation and commissioning to less than 18 months


THE ESRF-EBS UPGRADE LATTICE




Hybrid Multi Bend Achromat lattice features:

- Multi-bend for lower emittance: Longer and weaker dipoles => less SR
longitudinal gradient permanent dipoles and combined function magnets with low dispersion
- Dispersion bump for efficient chromaticity correction with $-\mathcal{I}$ transform:
Weaker, fewer sextupoles with partial compensation of aberrations for improved lifetime and acceptance
- Small beta functions in the central part of the arc
- ESRF-EBS design:
 $\varepsilon_x = 135$ pm.rad., Lifetime 20h, injection efficiency >90%

THE ESRF-EBS UPGRADE LATTICE



	Units	ESRF	ESRF-EBS
Energy	GeV	6	6
Circumference	m	844.4	844
Lattice		DBA	HMBA
Current	mA	200	200
Lifetime	h	50	25
Emittance H	pm.rad	4000	133
Emittance V	pm.rad	4	10*




31 magnets per cell instead of 17
 Free space between magnets (for one cell): **3.4m** instead of **8m**

EBS STORAGE RING MASTER SCHEDULE

Project start: January 2015

First idea 2012, white paper Nov 2012 , TDS (orange book) & council approval Nov 2015



Old ESRF-Storage Ring




ESRF-EBS




- October 2017** Start of girder assembly
- 10 December 2018** End USM, start shutdown
- Dismantling**
- Installation**
- 8 November 2019** Tunnel closed
- Tests & Injector restart
- 28 November 2019** Accelerator commissioning
- 2 March 2020** Beamline commissioning
- 25 August 2020** Start User Mode Operation

EBS COMPONENTS: MAGNETS




128 [132] Permanent
Magnet Dipoles

Assembled in
house



96 [100] Dipole-
quadrupoles

TESLA




64 [66]
Octupoles


BINP

More than 1000
Magnets

512
Quadrupoles
(128 [132] HG,
384 [392] MG)




TESLA (MG)
DANFYSIK (HG)



192 [196]
Sextupoles

DANFYSIK



96 [98]
Correctors





SEF




32 Cubicles for
DC-DC converters
to power each
magnet individually
COMECA

EBS COMPONENTS: DIPOLES

- Each dipole based on 5 PM modules
- Strength 0.67-0.17 T &
- Iron length 1788 mm
- 25.5 – 30.5 mm GAP
- Iron: Pure Iron
- Permanent magnet $\text{Sm}_2\text{Co}_{17}$



Around 6000kg of PM, 660 Iron modules



EBS COMPONENTS: VACUUM CHAMBERS

14 Chambers per arc

Anti-chambers for discrete pumping

No NEG coating except CH1, CH14

In situ bake-out

FMB, Pink
CECOM, Cinel

High profile aluminum
chambers (dipole magnets)

High profile stainless steel
chambers





Low profile stainless steel
chambers

High profile aluminum
chambers (dipole magnets)

High profile stainless steel
chambers


Low profile cross section

High profile cross section



EBS COMPONENTS: PHOTON ABSORBERS

- ~391 absorbers (including crotch absorbers, without injection cell specials) SAES_Rial
- Total power to be absorbed:
504.5 kW ($30 \times 15.795 \text{ kW} + 2 \times 15.314 \text{ kW}$)





Power density: 10 to 110 W/mm²
(normal to beam)

=> moderate power parameters
compared to current ESRF

- Scattered radiation blocked in the absorber to avoid chamber cooling

EBS COMPONENTS: GIRDERS



Four identical girders per cell


- **Motorized Z adjustment** resolution $5\mu\text{m}$
- **Manual Y adjustment** resolution $5\mu\text{m}$
- 1st natural frequency :
 - 50Hz (design criteria)
 - 49 Hz measured

128 + 1 Girders

- 4x32 (Arcs)
- 1 (Injection Cell)

Nortemeca
AVS


• Vertical movement



Motorized
Wedge
Airloc


Preload springs
(2x0.7T)

• Horizontal movement





Wedge
Nivell DK2

«Pushing
back»
spring (3.5T)



MOCKUP CELL



All components should be available to build a full cell in advance

Validate design and procurement:

- Debug technical and assembly issues
- Validation of the engineering prior series production
- Identify omitted and delayed components

Validate girder Assembly:

- Validate assembly process and tools
- Write assembly procedures (*specific alignment tools...*)
- Check assembly time
- Validate bake out process


Validate installation:

- Check installation process and tools
- Validate full cell installation including all equipment
- Validate tunnel layout


First arc under vacuum September 2017.

➔ *But was dismantled too early (May 2018) for space reason*



GIRDER ASSEMBLY



- Assembly building delivered in October 2017
- 3 assembly lines + 1 vacuum preparation line
- 3 to 4 girders assembled per week
- 128+1 girders assembled



ASSEMBLY PROCESS – ASSEMBLY LINES



LOGISTICS & STORAGE: A KEY ISSUE



Storage and logistics are key issues
for an upgrade



During dismantling, we need to store the new and the old machine outside the SR tunnel !!

LOGISTICS: BUILDINGS FOR THE ASSEMBLY AND INSTALLATION PHASES


ESRF 10-11-12-13

(200,500,300,700 m²)

Temporary building for:

- temporary storage
- old machine storage
- activation measurement

Outside storage for girders
(1000 m², 27km)



Chartreuse hall for (1200 m²):

- Dipole assembly
- Assembled girder storage
- Magnet fiducialisation
- Power supply preparation

Contractors buildings and area (500 m², 100 people)

ID14 (440 m²)
RF cavities

Temporary building storage (800 m²)

ESRF1 (1100 m²) Girder assembly hall
ESRF2 (2*500 m²) Storage buildings

LOGISTICS: COMPONENTS DATABASE

EBS Database

Home Database Tools
Assembly
Girders definitions

Family

Bellow

Component

Bellow CH12-CH13

Bellow CH2-CH3

Bellow CH9-CH11

Possible to assemble

Assembled

Components association

Quantity ordered	Delivery
102	27 / 102 26%

Quantity	Delivery
34	26%

Today

- 17000 Components for the tunnel
- 2650 Components for the technical zone

But still work in progress to integrate all components

- SAT progress
- Assembly schedule
- Assembly components preparation
- Assembly follow-up
- Installation preparation
- Installation follow-up
- Commissioning follow-up

Database daily updated

- Type
- Quantity
- Delivery date
- Status
- Serial number
- Location
- ...

➡ ...FAT,SAT, ready for assembly

Now fully used for the operation


FAT: Factory Acceptance Test
SAT: Site Acceptance Test

BENEFIT FROM PHASE 1: INFRASTRUCTURE UPGRADE



Experimental hall extension expertise:

- *New buildings*
- *Expertise of 5 months long shutdown*
- *Expertise on restart accelerators and beamlines*
- Upgrade of the electrical mains distribution
- Upgrade of the water cooling system and chillers
- Installation 1 μ m filters at the entrance of the 32 cells
- New High Quality Power Supply to improve mains quality
- Renovation of the EXPH Roof Membrane






BENEFIT FROM PHASE 1: DEVELOPMENT OF ACCELERATOR COMPONENTS

- Upgrade of BPM electronics
- 6 m long straight sections
- 7 m straight sections
- SSA RF Transmitters
- HOM damped RF Cavities
- Cryogenic in-vacuum undulators
-



- BPM system ready for EBS
- Expertise in vacuum chambers and magnet development
- Expertise in installation
- Expertise in power supply
- RF design ready and validated for EBS




- Upgrade of the injector for topup operation (*BPM electronics, quadrupole movers, two additional RF cavities, linac upgrades, new booster magnets power supplies, bunch cleaning system*)



Injector ready for EBS

[Girders moved during shutdown by 17.5 mm, radial, for the new RF frequency (+172 kHz)]





PRIOR SHUTDOWN: VALIDATION OF NEW DIAGNOSTICS

New Beam loss monitors installed and commissioned on the old machine:


- 4 BLDs per cells
- Get references to be compared to the new machine

New tune monitor installed and commissioned on the old machine






Complementary Spark BPM electronics validated on the old machine
complementary to the existing Brilliance electronics
(6 brilliance, 4 sparks per cell)

Implementation of the new timing system



PRIOR SHUTDOWN: ANTICIPATED TASKS

- **A new distribution of LN2 for cryogenics in-vacuum undulators.**
- **Installation of VDC distribution for power supply**
260 cables installed - 24 870 m – during Machine shutdowns only
- **Reorganization of the cabling in the cubicle**
Separation of tunnel cables from others to ease the dismantling
- **Cleaning of the technical zone**
*Clearing out the working areas
 Mark and sign post
 Prepare sorting areas & boxes*



DISMANTLING + INSTALLATION: DEC 2018 – NOV 2019

Dismantling

Civil works

Girder entry Vacuum connection

Piping Cabling

FE


Straights Sections Bakeout

IDs

Equipment test

PSS test

Alignment & Global tests



+ all the activities in the technical areas

- Dismantling done in 2 shifts
- Installation done in normal days + late evenings for roof opening/closure

LOGISTICS: HANDLING

Crane operations:

Dismantling: 3 Cranes in 2 shift for dismantling + forklift operators

Installation: 2 Cranes in shift + 1 normal day + forklift operators

→ Pick load of 40 handling staff

→ \approx 5000 opening/closing during the project (equivalent of 30 years of ESRF operation)

→ No specific shutdown of the overhead cranes thanks to specific maintenance plans.

Tools:

Many special tools designed for the EBS project, but also new procedures: it will partially help us for the operation of the new machine.



LOGISTICS: SPECIFIC TOOLS TO MOVE THE GIRDERS

Capacity of the existing cranes was not sufficient for the installation of the new girder

2 Gantries for
3 entrance points



Rollers in experimental hall



Girder moving tool




2 modules inside the tunnel for final
installation at ± 1 cm (2 spare modules)

EBS installation



ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc


10 December 2018



ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART OF USER OPERATION , ALBA Seminar September 27 2023, Revol Jean-Luc

10 December 2018

ESRF-Storage Ring



10 December 2018



ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc

Dismantling in the tunnel



ERF-ERS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



ESRF-EBS IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc




ESRF-EPS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



ENGINEERS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc

Non activation measurements



ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc

Civil work



ESRE-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



ESBE-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc

Installation of the girders



ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTAINTS
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART¹
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



FSRF EBS IMPLEMENTATION, PERFORMANCE AND RESTART.
OF USER OPERATION, ALBA Seminar September 27 2023,
Revol Jean-Luc





ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc




ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc

Interconnection of the girders and special chambers



ESRF-EBS IMPLEMENTATION, PERFORMANCE AND RESULTS
OF USER OPERATION, ALBA Seminar September 27 2023,
Revol Jean-Luc



Collimators


ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTRAINT
OF USER OPERATION, ALBA Seminar September 27 2023,

Revol Jean-Luc

Piping & Cabling




ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



PSRF-EBS IMPLEMENTATION, MAINTENANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27, 2023

Revol Jean-Luc

Straight sections Reconstruction




ESRF-EBS IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION, ALBA Seminar September 27 2023,
Revol Jean-Luc




ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27, 2025,

Revol Jean-Luc





ESRF-EBS IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION , ALBA Seminar September 27 2023,
Revol Jean-Luc



RF-EBS IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION, ALBA Seminar September 27 2023,

Revol Jean-Luc


Ready for startup



ESRF-EBS: IMPLEMENTATION, PERFORMANCE AND RESTART
OF USER OPERATION / ALBA Seminar September 27 2023
Revol Jean-Luc

ESRF-EBS
November 2019

CONTRACTORS STAFF ON SITE



**132 300 hours i.e more
than 16 500 days of works
in less than 11 Months**


SHUTDOWN FOLLOW-UP

During the whole shutdown, took place :

- Daily meetings with the ESRF staff directly involved
- Weekly meetings with the sub-contractors working on site
- Weekly project report meeting to ESRF staff (*usual operation meeting kept*)
- Every 2 weeks project report to the director board (*usual directors meeting*)

Daily meeting was the occasion to :

- Update the status of the tasks ongoing
- List the tasks for the coming days and week
- React in case of unforeseen event or difficulties
- Update and adapt the Master Planning in accordance to the last information received



SHUTDOWN PROGRESS

So far we had no need to largely modify the planning.


In general we have had all the tasks completed slightly ahead of schedule, but the start of sub sequential ones were usually locked by many constraints (availability of resources, tooling, safety etc) and in general cannot be changed.

Only the final tasks in the last zones (*in particular SRTU4 that is the last one to be completed*) were in the critical path, so they could directly affect the tunnel-lockout date.

Given the fact that:

- ✓ The most critical phases from a technical and logistic point of view have been dismantling and girder roll-in
- ✓ The remaining tasks were in general proceeding slightly faster w.r.t. plan (in particular vacuum, front-end, TZ, piping and cabling installation)
- ✓ Piping and cabling tasks strongly depending on external resource cannot be moved
- ✓ Coactivity, safety issues and rare resources management are the drivers of the planning

SR1
SR2
SR3
SR4
SR5
SR6
SR7
SR8



CRITICAL ITEMS FOR THE INSTALLATION

✓ Injection cell

The injection cell, which is different and more complicated, was treated as an independent project (with dedicated planning), was just on time in the design and procurement (including equipment outside tunnel).

✓ Ceramic chambers


The design and procurement of those complicated chambers was late and are still a week point for the machine.

✓ Collimators


The procurement of those complicated equipment was just on time) due to a complicated design and manufacturing.

✓ DC-DC converters


The procurement and qualification of those components were longer than foreseen.



Commissioning



Commissioning



ESRF-ERS: IMPLEMENTATION OF PERFORMANCE AND RESTART OF USER OPERATION Seminar September 27 2023, KEK DESY

AVAILABILITY OF SERVICES DURING SHUTDOWN

Electricity



- Wall plug always available
- 400 V mains not available during dismantling and cabling & piping tasks, available during test periods prior SR cabling
- Full power from tunnel closure

Fluids

- Deionized water (SRE) available after piping task
- Reduced flow (SRE) available in Labs, technical rooms, and booster prior the end of SR piping
- Compressed air & Nitrogen networks available after completion of piping tasks
- Industrial water cooling always available


Control system

- Computing network + Wi-Fi available after dismantling period
- WI-FI requalified in the tunnel when most of equipments are installed
- Control System available after dismantling period (outside specific CS development and debugging periods)






ESRF-EBS: EQUIPMENT TEST AND STARTUP

- **Control software, optics tools, commissioning scripts validated** prior and during shutdown on the Storage Ring simulator
- **Low and high level control for all equipment** (including vacuum):
 - ➔ Started as soon as the cabling is done
- **Power test of the magnets** from August to November with tunnel not accessible
- **During last weeks of the shutdown with tunnel close** (14/10 to 28/11):
 - ➔ Final alignment & survey
 - ➔ Validation of the personal safety system
 - ➔ Global power test of the magnets
 - ➔ Interlocks
 - ➔ Injection/extraction elements
 - ➔ Radio-frequency power commissioning
 - ➔ **Injector commissioning**




INJECTOR COMMISSIONING


- A lot of upgrade during Upgrade phase 1
- Substantial work during shutdowns
 - Reduction of booster circumference*
[Girders moved during shutdown by 17.5 mm, radial, for the new RF frequency (+172 kHz)]
 - Upgrade of septa*
 - Adaptation of transfer line 2*
- Operation off-energy
 - Only part of booster reduction was applied to the reduction*
[40kHz mismatch, -1.4% off-energy]
 - ex: 120 nm \rightarrow 85 nm*
- Operation with emittance exchange
 - Fast tune vertical tunechange with power supply
 - H beam size reduced by 40%
 - V beam size increased by 3
 - Injection efficiency improved by 5-10%
- Commissioning performed in a few days




ESRF-EBS: BEAM COMMISSIONING




November 28th
First turns




December 6th
Beam stored




December 15th
Accumulation



January 30th
First Beam on 26 Beamlines




February 28th
200 mA achieved



3 physical obstacles on the beam path and poor vacuum in a few ID NEG coated chambers slowed down the overall commissioning.


ESRF-EBS: BEAM COMMISSIONING




Obstacle in Cell-5 Ch7
AL piece fall during
installation of DQ2



Piece of wire
accidentally into SS-23
ID chamber



3 physical obstacles on the beam
path found during commissioning.




Installation mistake
Cell8-Bellow 9-11



Detected, get around, resolved by:


- Very useful beam loss and turn by turn BPM diagnostics
- Bumps, non-closed injection bump, off-energy operation, distorted close orbit,...
- Intervention to remove the obstacles one by one
- Largely beneficial to injection efficiency, lifetime, optics tuning

ESRF-EBS: BEAM COMMISSIONING



A Few ID NEG coated ID chambers with poor vacuum


ID12 was contaminated → poor vacuum → replaced



Detected, resolved by:


- Very useful beam loss diagnostics for detection
- Intervention to exchange the chamber
- Lifetime increase by a factor 3

ESRF-EBS: BEAM COMMISSIONING






Optics tuning:

- Optics correction** (magnet modeling)
 - Add magnetic cross talk between adjacent magnets
 - Correct wrong calibration factor
 - Excellent alignment of components (<50 μm in both plane)
- Orbit steering**
 - Beam base alignment (100 μm rms both plane)
 - Eigen vector optimization (from 64 to 162)
 - Eigen mode analysis (correction of DQs missing angle)
- Lattice re-correction after SB and 2PW installation
- Coupling correction** ($\varepsilon_v < 1\text{pm.rad}$)
- Dynamic aperture and injection efficiency studies (Still lower than model)
- Automatic **lifetime/losses optimizer** (sextupoles, octupoles, skew scanning)



$\Delta\beta/\beta > 1.5\% \text{ H,}$
 $1.5\% \text{ V,}$
 $\Delta\eta \sim 0.7 \text{ mm H,}$
 0.7 mm V
IE 80%

ESRF-EBS: BEAM COMMISSIONING




BM sources:


- No BM sources at the start of commissioning
- Most of the sources installed during shutdown
(First installations done on a running machine)
- **Optic readjusted** after each installation
- Installation delayed due to lock-down
Delay in the beamline commissioning
Necessity to run one shift at low current for initial RP validation

25 February MDT	BM 05	2PW
25 February MDT	BM 16	SB
March 8 MDT	BM 29	2PW
March 8 MDT	BM 30	SB
June Shutdown	BM 01	2PW
June Shutdown	BM 02	SB
June Shutdown	BM 08	SB
June Shutdown	BM 20	SB
June Shutdown	BM 31	2PW
June Shutdown	BM 32	SB
August Shutdown	BM 23	2PW
August Shutdown	BM 25	2PW
August Shutdown	BM 26	SB
August Shutdown	BM 28	SB
October Shutdown	BM 07	2PW
October Shutdown	BM 14	2PW
October Shutdown	BM 18	3PW



ESRF-EBS: COMMISSIONING FROM 28/11 TO 01/04



ESRF-EBS PERFORMANCE: LIFETIME




ESRF-EBS PERFORMANCE: LIFETIME




- Still conditioning
- Reaching lowest measurable limit at some locations

ESRF-EBS PERFORMANCE: ELECTRON BEAM LOSSES ON THE INVAC IDS

- Electron beam losses localized at two shielded collimators for radioprotection safety and to protect IDs
- Efficiency of the relocation: 50% (instead of the design 80 %)
- Collimators set for 5-10% beam lifetime reduction
- Today losses at IDs are similar to the previous machine
(*better lifetime with conditioning and optics tuning*)




ESRF-EBS PERFORMANCE: BEAM STABILITY




- Close orbit corrected down to 50 μm in both planes
- Residual AC motion at ID centers with **fast orbit feedback**:
 - 0.8% of horizontal beam size
 - 2.8% of vertical beam size


- ✓ *Despite the reduction in the horizontal emittance, the beam stability fulfils today the beamline requirements*
- ✓ *Task force established to monitor and further improve the beam stability against different sources of perturbation*




ESRF-EBS PERFORMANCE: INJECTION PERTURBATION BY KICKERS AND SEPTA




Kickers OFF



Kickers ON



Horizontal
compensation ON



Horizontal and Vertical
compensation ON

- Off-axis injection scheme very similar to the one of the previous machine proved to be very efficient for the commission and the restart but:
- Perturbations of the closed orbit during top-up injections and a greater sensitivity of the beamlines due to the reduced beam size of the stored beam prevent some beamlines from acquiring data and consequently limits today the full exploitation of EBS
 - ✓ Top-up frequency reduced from one every 20 minutes to one every 1 hour to limit disturbances
 - ✓ Septum compensation is efficient
 - ✓ Kicker power supplier upgrade (slow ramping) and feedforward compensation are effective but not sufficient
 - ✓ New injection schemes are under evaluation

ESRF-EBS PERFORMANCE: LIMITATION IN CURRENT

Intensity limited for timing modes (i.e. high intensity / bunch)

- Abnormal temperature of the ceramic chambers observed,
- K3 chamber broke when ramping in 16 bunch

Existing ceramic kicker and shaker chambers fragile:
present design does not withstand thermal stress


→ Cause: assembly from several parts with glazing joints (bubbles)

Delay in the procurement of new chambers

→ impose to implement a mitigation strategy


increase of the coating (reduced impedance) thanks to the implementation of slow ramping kicker power supply

- Additional spare, with original design is difficult to procure
- New design deliveries should allow installation in 2024



Existing Kickers: Original Design

Additional Coating -> reduce
power / stress
Additional Spare




New Kicker Design : One Single Piece


Eliminate ceramic junction
All 4 same geometry



ESRF-EBS: USER MODE OPERATION



Filling modes (2023)



**USM resumed on
25th August 2020
at 8:00
as initially
planned**

	7/8 + 1	Uniform	28*12+1 (Hybrid)	16 bunch	4 bunch
I_{max} (mA)	192+8	200	192 + 8	75 (90)	40
Lifetime (h)	> 20	~ 25	> 16	~ 5.5	~ 5
ε_v (pm)	10	10	20	20	40
Reached	13/09/22	21/11/20	14/11/22	23/08/22	05/12/22

- *Intensity limitation due to mechanical weakness of the kickers ceramic chambers*
- *Vertical emittance artificially increased from 1 to 10 or 20 pm rad for an operational lifetime*
- *All timing modes delivered with a purity of 10-9 with cleaning process in the booster*



ESRF-EBS: RELIABILITY

	2017	2018	2020 <i>EBS</i>	2021 <i>EBS</i>	2022 <i>EBS</i>	2023 ⁽⁰⁷⁾ <i>EBS</i>
Availability (%)	98.3	98.5	96.1	96.4	99.1	99.3
Mean time between failures (hrs)	64.3	104.3	46.0	66.4	88.5	121.7
Mean duration of a failure (hrs)	1.11	1.60	1.80	2.42	0.83	0.8

- **Overall reliability comparable to that of the old source**
- Magnet power supply system was the most complex hardware to develop and commission
- Operation disturbed by a few long failures from sub-systems not directly linked to EBS design
 - ✓ *aluminum NEG coated ID vacuum chambers, RF master source, 20 KV high voltage cable defect, cavity couplers, cryo-invacuum undulators*
 - ✓ Two problems of copper deposits in the SR cooling:
 - *Copper clogging in the magnet flow meters → now reduced by regular checks of the flowmeters and by improving the absolute filtration in all cells.*
 - *Copper deposits in the absorber needle valves → temporarily solved by increasing the flow rate and modification of the circuit*

ESRF-EBS: RELIABILITY

	2017	2018	2020 <i>EBS</i>	2021 <i>EBS</i>	2022 <i>EBS</i>	2023 ⁽⁰⁷⁾ <i>EBS</i>
Availability (%)	98.3	98.5	96.1	96.4	99.1	99.3
Mean time between failures (hrs)	64.3	104.3	46.0	66.4	88.5	121.7
Mean duration of a failure (hrs)	1.11	1.60	1.80	2.42	0.83	0.8



- **Only 1.6% of refill skipped (2022)**



RADIATION DAMAGES IN THE NEW STORAGE RING

Some equipment are already suffering from radiation damages around the straight sections equipped with Aluminum NEG coated vacuum chambers.

- *Aging of HLS captors of girder1*
- *Increasing number of faulty ion pump cables*
- *Change in color, degradation, brittleness of insulating of cables*

Several actions implemented:

- *Visual inspection of the cables to follow-up their status*
- *Identification of the damaged devices*
- *Installation of lead shielding on HLS captors and FE photon shutters*
- Replacement of damaged cables
- Installation of additional lead shielings



ENERGY SAVING WITH EBS

ESRF ENERGY CONSUMPTION OVERVIEW


Electricity consumption

before EBS =

65 350 MWh



after EBS =

53 000 MWh (-20%)



ESRF-EBS: IMPACT OF COVID-19 PANDEMIC

- Commissioning of the SR completed when the first lockdown was declared in France.
- The two-month restrictions impacted heavily the beamline commissioning.
- During the second and third lockdowns, number of user shifts reduced.



August 2020

USM



MDT

Limited access to the site:

- *Opportunity to implement tools for remote control*
- *Development shift/interventions often performed via video-conferencing*
- *Very efficient for short and fast support*




Beamline test

LESSONS LEARNED: SPECIFICITY OF AN UPGRADE


Life of an institute like ESRF and ALBA:

Starts with a green field project



Continuous development program

Large Upgrade



Green field Development Upgrade

<i>Pressure from users</i>	+	+++	+++++
<i>Planning and issue date</i>	+	+++	+++++
<i>Buildings & infrastructure</i>	+++++	+	+
<i>Space management</i>	+	+++	+++++
<i>Qualified staff and expertise</i>	+	+++	+++++
<i>Budget</i>	+++	+++	+++

LESSONS LEARNED: TECHNICAL ASPECTS

- ✓ Large benefit from phase 1 upgrade for the infrastructure and accelerator components
- ✓ Capitalize on the expertise for installation and start-up gained on the existing facility prior upgrade (*staff, procedures, control...*)
- ✓ Pre-assembly and anticipated tasks as much as possible executed prior the shutdown
- ✓ Design, procurement and installation procedures validated on the mockup
- ✓ Activities concentrated on the storage ring during installation, limited activity for beamlines & infrastructure
- ✓ Validation of control and tools on a simulator
- ✓ Equipment test started as soon as possible before startup. including control system
- ✓ All systems (RF, diagnostics, power,..) should be operational and reliable from start of commissioning
- ✓ Efficient beam position monitor and beam loss detectors available from the start of commissioning



LESSONS LEARNED: PLANNING AND DECISION MAKING

We did (and re-did) a few time the planning !!.....
But the master planning never changed

- Planning should remain simple with the main tasks and managed by one person present during all the project [*EBS: MS project 6323 lines for the 32 cells*],
detailed planning of each tasks should be managed by the technical groups,
management of the critical resources is the driver
simple web access to the data base for all staff,
status of macro tasks updated by the technical groups.
- The project organisation will evolve and adapt according to the project phases but the core people involved from the beginning should be kept.
- Fast and efficient escalating decision making is mandatory to keep the planning objective and the efficiency

LESSONS LEARNED: PROJECT AND OPERATION

- Operation is the priority.... And ...Project is the priority....
Impossible to separate it ...same people involved

Issues popping up from the operation often require immediate actions which disturb the upgrade progress

- No need to separate and dedicate people only to the new project, staff should remain involved in the operation in order to guarantee the quality of the delivery and the ongoing development of the present machine.

....

But the operation should also be delegated to the younger staff and less expertise staff in order to train them and give more time of the experts to work on the project.

- Everybody will finally move from the operation of the present machine to the construction and operation of the new machine

LESSONS LEARNED: HUMAN ASPECTS

- ✓ Stress and queries is obviously coming from the fact that we stop and destroy a nice and performant running machine with the objective to built a new and challenging one !
 - ✓ Upgrade is also associated to a change of generation
 - Recruitment wave of new staff
 - Retirement wave (usually waiting the end of the project)
 - Creation of a new expertise
 - A chance to update (or get !) the documentation
 - A chance to modernize the working methods (data base...)
- ✓ Upgrade is a fantastic occasion to reinvigorate the institute

LESSONS LEARNED: SPECIFICITY OF THE TDR

For EBS the TDR phase was (extremely) **short**, [but we had the upgrade phase 1]:

- First idea 2012, white paper Nov 2012
- TDS (orange book) & council approval Nov 2015
- Project kick-off Jan 2015
- First Magnet CFT July 2015.



With more time, TDR should not only give a technical design report produce by a reduced number of persons but should allow:

- Fix and distribute a reference lattice
- Select technical and engineering solutions (*start drawings which is time consuming,..*)
- Built prototype of critical devices (*not done for EBS*)
- Select the logistics solutions (*storage, transport, preassembly, start the administrative process..*)
- Organize the procurement (*prequalification, preparation of specs..*)
- Elaborate a first planning
- Elaborate the project implementation organisation and team
- Start to recruit new staff (*new temporary positions, anticipation of retirements,..*)

As much as possible should be ready before the realisation is launched

Modifications and adaptation are difficult later due to the interaction between the hardware components and the interactions between the tasks.

The exciting and challenging part begins really with the start of procurement ...with the obligation to built a new running performant ... with no possibility to step back !!

ESRF-EBS: CONCLUSION AND PERSPECTIVES

Main results:


- Dismantling and installation on schedule
 - Fast equipment and beam commissioning of the new source
 - Despite the impact of Covid-19 pandemic, users received back the beam on the scheduled day.
 - Main performances achieved (beam current, beam modes, lifetime, emittances, stability)
 - Excellent reliability of the equipment
- Beamlines are now taking full benefit from the source, and continue to develop and upgrade

Today objectives for the source:

- Fine tuning and follow-up of beam parameters, including beam stability
- Implementation of the hot-swap system for the power supplies
- Minimize injection perturbation and revise injection frequency if needed
- Nominal beam current in time-structured modes

The operation oriented projects:

- New ceramic chambers
- Solid-State Amplifiers (SSA)
- 4Th Harmonic cavities
- Injector upgrade
- Mini-beta optics



ESRF-EBS: PARAMETER ACHIEVED

	Design	Realized today
Total current	200,90,40 mA	200, 75, 40 mA
MTBF	> 30 h	> 100 h
Up-Time	98%	> 99 %
Injection Efficiency	> 90 %	> 70 %
Lifetime	> 20 h	> 20 h
ϵ_H	< 140 pm rad	< 130±20 pm rad
ϵ_V	10 pm rad	10 pm rad
Stability	< 0.05 σ	< 0.01 σ

BEAMLINE UPGRADE (STILL IN PROGRESS)

Four new beamlines fully optimized for EBS

- EBSL3-BM18: *High throughput large field phase-contrast tomography beamline*
- EBSL8-ID29: *Serial crystallography beamline*
- EBSL1-ID18: *Beamline for coherence applications*
- EBSL2-ID03 *Beamline for hard X-ray diffraction microscope*

ESRF Data Policy on all beamlines



New BL control system



New access modes BAG, mail-in, etc...




Refurbishment Programme

ID18 (ID14), ID21, ID24, BM23
ID26, ID27, BM29, ID32

10 new high-end 2D detectors




New insertion devices



MANY THANKS FOR YOUR ATTENTION



Many thanks to all ESRF and external personnel that has been working with great enthusiasm and results for this project



Courtesy for the presentation material:

JC Biasci, N Carmignani, T Brochard, L Hardy, I Leconte, S Liuzzo, T Marchial, P Raimondi, S White