


SOLEIL RF Systems

Lu ZHAO, on behalf of RF/LINAC team



ESLS RF Workshop and the HarmonLIP Workshop ALBA Synchrotron

22-24 Oct. 2025





From Soleil to Soleil II — Climbing Higher Together



Outline



Current SOLEIL machine


- A. Machine and RF status
- B. Experience with the SOLEIL 352 MHz updated SSPA's
- C. LINAC
- > SOLEIL II with double RF system (352 MHz and 1.4 GHz)
 - A. NC HOM-damped cavities
 - a) Main cavity and power coupler
 - b) Harmonic cavity (passive then active if necessary)
 - c) Instabilities Predicted
 - B. RF control & Supervision system (Digital-LLRF system)
 - C. Longitudinal bunch-by-bunch feedback
- ➤ Testing and validation of SOLEIL II cavities on the current SOLEIL SR

RF test stand






SOLEIL Beam Availability







Duration of beam availability incidents over the course of 2025



- Power supply
- Fire incidents
- Amplifier control issue
- Others (false RF problems)






Power Amplifier Upgrade

Status

2 x 60 kW BOO SSPA's and 2 x 200 kW SR SSPA's completed



Upgraded AMP2 (4 x 50 kW towers)

Storage Ring Power supply upgrade plan


From beginning of 2024, 1 x 50 kW tower will be installed every 2-3 months in the SR to benefit from four fully upgraded 200 kW SSPA'S by mid 2027 for SOLEIL II.





FIRST Fire on RF Power Amplifier

First fire outbreak in one of our old RF power amplifiers, 11/2024












Labo Test





Key Findings


- LMR400UF FR and LMR400FR deliver excellent thermal resistance and RF endurance, drastically lowering the probability of ignition.
- Adding FR heat-shrink to existing LMR400 UF also addresses fire-propagation risk at a very attractive cost while preserving <u>excellent flexibility</u>.

Solution	Cable type	Flexibility	Cost
1	LMR400UF FR	-	54% more expensive
2	LMR400FR		Expensive
3	FR heat-shrink on existing LMR400 UF	++	69% Less expensive

Conclusion: option 3 is the best compromise. Decision of equipping all power cables with FR heat-shrink over 18 months.







Even the best technology can't protect me from my own clumsy mistakes.





Back to operation:

 2 hours downtime: back to operation with 450 mA using 3 out of 4 amplifiers.

Using 3.5 amplifiers (0.5 amplifier = 2 towers) for 500 mA operation for 3

months

Decision:

- 1. Reduce from 18 down to 8 months the power cable modification plan
- 2. Increase the frequency of thermal inspection with IR-camera
- 3. Improve sensitivity of fire detection system






For Reasons that Remain a Mystery

Frequent trips due to amplifier power drop (8 over 2 days)

- LLRF increase power output
- Reflected power increased (tuners detuned)
- •AMPLI 1–3 compensated → Reflected power triggered interlock on AMPLI 4
- •5 × 3kW AC-DC converters damaged



The additional RF switch in the upgraded power amplifier is suspected!



The operation becomes normal after removing the « RF switch » Labo test of RF switch doesn't show any issue. Further investigation of the RF switch during the next machine session in real operation conditions.




Water Leak in LINAC



RF Window Cooling Pipe Aging







LINAC

Project Buncher with Thales AVS



FAT: 2024 September

SAT: Next technical stop during 2025

Dec. to 2026 Jan.

Project Modulator (JEMA) + Klyston












 Increase LINAC energy from 110 MeV to 150 MeV to adapt BOOSTER in SOLEIL II by increasing the power of S1 and S2.(10 MW to 20 MW)



In case of a failure of one or the other klystron, two waveguide switches (SW1, SW2) allow to maintain the power in LINAC. The objective is to reach 150 MeV, which insure a correct injection into the future Booster.






352 MHz Fundamental Cavities

Fundamental system - 5 x 352 MHz HOM-damped cavities

- Final Design Review last summer with the latest improvements
- Ongoing studies with Institut de Soudure to test brazing samples of absorber ferrite and define the acceptance criteria



Microsonic scan of a ferrite plate sample

- Tuner CFT launched in mid-September (8 tuners expected by May 2026)
- Ancillaries CFT's (pick-ups, support frame...) to be launched by November 2025

250 kW FPC's: built in the framework of a collaboration with CERN; first prototype under power tests at APS.






352 MHz Fundamental Coupler


 Lengthening of the antenna + depth penetration and loop rotation parametric study → With a loop insertion depth of 0 mm, the coupling factor (β) reaches a maximum of 7 at 90° and becomes 1 at 21°.


(The loop is flush with the cavity edge for 0 mm depth penetration and is parallel to the H-field for 0° rotation angle.)



9.196

Insertion depth: 1-5 mm










1.4 GHz Harmonic Cavity


 Designed in the framework of a collaboration with ESRF(presented by Pavel Borowiec)



- Objective: Call for tenders for 3 x HC's
 - ➤ Delivery of first HC mid-2027
 - ➤ Conditioning of the first HC in test area in fall 2027
 - ➤ Installation and tests of first HC in SOLEIL by beg. 2028
 - Launch fabrication of the 2 remaining HC's



Instabilities Predicted by mbtrack2



In the left corner is the **PTBL instability** area (green) for high ξ and I_b .

There is a stable area in between the PTBL and LCBI ones.

Unfortunately, it is significantly reduced by the **Coupled D-Q instability** (red area), which limits the achievable lengthening at lower current.

In the right upper corner, instability occurs (dark purple) but has not been analyzed yet. It might be LCBI.

Tracking with direct RF feedback on MC

4 MCs (V₁ = 1.7 MV, optimum tuning) 2 passive 1.4 GHz HCs (R_s = 0.9 M Ω /cav, Q_o = 31000)

Worst case for the MC HOM (8.8 kΩ at 1.7 GHz) and for the ID's, which are all open

- ➤ Simulations with MC voltage optimization are under progress and first results with 1.4 MV instead of 1.7 MV on each MC and DFB gain optimization show stable areas for ξ ≈ 1 and currents down to 300 mA.
- Mode 0 phase feedback is being modelled to cope with Coupled D-Q instability





LEIL A Backup Plan for Coupled Bunch Instabilities

- Longitudinal Bunch-by-Bunch Feedback study → the specific dedicated team (AP/RF/Diag/ISAC) to FBT/FBL has been set up in beg. 2025
- Collaboration with BESSY/Diamond for electronic system
- FBL kicker designs
 - Over-loaded cavity (Micha Dehler, SLS 2.0)
 - Resonant Stripline kicker (Nakamura Takeshi, KEK)

An RF expert is welcome to rescue the kicker design before it kicks back!















RF Control & Supervision system





Digital LLRF System



FMC LXD31K4-DC 4 channel 16-bit ADC/DAC (Logic-X)

FMC 4-Channel RS485/RS422 Module HTG-25PMD-SMB




DAMC-FMC2ZUP (CAENels)

The cavity tuner is controlled completely by a cross-compiled C program which is running in the PS of the ZU+.

This function was successfully tested on the machine, with the full beam loading.

The ChimeraTK firmware from DESY is also implemented in order to communicate with the TANGO control system.

The DLLRF system will be installed in the booster at the end of 2025 and in the storage ring in mid-2026.










352 MHz and 1.4 GHz Test stand








Overview of the New Test Area





Test Area: RF Bunker






2 x 352 MHz Cavities in SOLEIL

Work Description:

- Conditioning of 2 x 352 MHz power couplers in the test area En of Summer 2026
- Conditioning of the 2 first 352 MHz cavities in the test area Fall 2026
- Disassembly of CM#1 and replacement by the 2 new cavities Mid 2027
- Use of SOLEIL II DLLRF system and upgraded SSPA's from mid 2026 onwards
- Test and validation of the two new RF plants with beam up to 500 mA 2027/2028
- Shutdown of summer 2027 is considered to install the cavities.





RF Planning for SOLEIL II

- A multi-year RF roadmap, with specific construction milestones
 - RF conditioning: August 2026-Shutdown
 - MC (main cavity) and HC (harmonic cavity) testing in the present storage ring + DLLRF

Aug. 26 RF Bunker ready Aug 26 / Dec. 26 RF Conditioning -300 kW Coupler - First 2 RI 352 MHz Cavities July-August 27
Installation in
SOLEIL SR of
the 2 first RI 352
MHz Cavities

Fall 2027

RF Conditioning

-1st HC cavity

- Cont. of RF
systems

January 2028
1st 1.4 GHz HC installed into SOLEIL

Shutdown of SOLEIL

October 2028













In parallel to operation
Stored Beam reduced to **450 mA**

3-6 months for validation 3 more cavities to manufacture

RF conditioning of the 3 other MCs

Fall 2025 New DLLRF in operation for Booster Summer 2026 New DLLRF in operation for SR Construction, then RF conditioning of the 2 other HCs





Thanks for your Attention!

